

## **Networking for EISCAT-3D**


**EISCAT-3D** stakeholder meeting

17 October 2019

Lars Fischer < lars@nordu.net>

### **RECAP**

(from March stakeholder meeting)






## Network Topology: a Ring




- Existing fibre Tromsø-Narvik-Kiruna-Kalix-Sodankylä
- New Fibre Tromsø-Skibotn-Kilpisjärvi-Karresuvanto-Sodankylä
- Site optical and IP equipment
- Allow future connectivity to HPC facilities in SE, NO, FI



#### Routed IP Network



- Inter-site connectivity: an EISCAT-3D "LAN" connecting the local networks of the sites
- NREN uplink:
   Ring connects to each of the national networks for upstream traffic
- Total, aggregate ring capacity: 100G





# Alternatives (New and Better Technology)


#### Moving data to Data Centre



- Connect the Ring Buffer nodes secondary side to DC
- Aggregate Receivers data ethernet ports and extend to DC
- Extend Receivers ethernet ports to DC
- (order of *more* flexibility, capacity, and cost, *less* equipment at sites)


## Original Design






#### 2x100G Point-to-Point Ethernet













Ring Buffers at DC. 40x100G Ethernet per site directly to DC Optical network protection

### Ring-buffers at D.C. (2)





Ring Buffers at DC. 60x100G Ethernet per site directly to DC Optical network protection



Location of DC for illustration only Can be FI, SE, NO – but must be close to ring

# Comparing the Alternatives



Alternative	Pro	Cons	Cost Delta
Original design with IP connectivity	IP full redundancy. Can be used for normal Internet	One interface handoff to the site. Only planed for 64Gbps of traffic to DC per site.	
2x100G Ethernet directly to DataCenter	Two interface handoff to DC. 2x100G of traffic to DC when all fibers are whole.	All internet traffic needs to go to the DC.	Slightly cheaper; no routers at sites
Ring Buffer at DC, 40x100G transport	All server can be placed at DC. Reduce size & power at sites.	All internet traffic needs to go to the DC.	+ ~1.400k€
Ring Buffer and aggregation switch at DC, 60x100G transport	All possible traffic from receivers can be transported to DC. All server can be placed at DC. Reduce size & power at sites.	All internet traffic needs to go to the DC.	+ ~2.100k€

#### Caveats



- Designs shown to indicate possibilities
  - Technology that has only recently become available
  - Changes in optical networking cost
  - Not fully engineered or tested
  - Not costed in details
- Impact on annual service cost not assessed
  - Optical (and point-to-point) equipment have longer lifetime
  - Fewer equipment replacement needed (with un-changed requirements)
  - 10-year system lifetime realistic
- Work remains on the details
  - ... if EISCAT find the idea interesting



# **Outstanding Issues**

#### Questions & Concerns & Next Steps



- Should we go ahead with the new options
  - Which one?
- Data Centre
  - Where?
  - Include in network?
- Securing local fibre
  - Need to place SE and FI orders; Existing fibre offers have formally expired
  - Need to confirm sites
  - Can we confirm Kaiseniemi? Please?
- Network build
  - Fibre & optical network build
  - Integration with chosen computing setup



# Thank You

<lars@nordu.net>




# **Backup Slides**


# Aggregate and Extend Receivers ethernet ports to DC


- The receiver modules, 119 at each site, has 2x25Gbps SFP+ ethernet ports.
- The the ethernet ports are terminated in a switch and the ring buffer servers are connected to the same switch.
- The Ring Buffers secondary side are connected to another switch and the output from that switch is connected to the DC on 2x100G where each 100G goes on a different path on the DWDM ring.

### Logical view Site 2x100G to DC



## 2 x 100G from Site directly to DC







# Aggregate and Extend Receivers ethernet ports to DC


- The receiver modules, 119 at each site, has 2x25Gbps SFP+ ethernet ports.
- The the ethernet ports are terminated in a switch and the ring buffer servers are connected to the same switch.
- The switch can stay at the site and aggregate the the traffic from the receivers as each receiver are not producing more than 2x16Gbps. The ring buffer servers can then be moved to a DC and the optical network is used to forward the aggregated Ethernet from the receivers to the DC.

# Antennas at site with aggregation switch, Ring buffer nodes with deaggregation switch at DC


Logical view (reduces waves on the optical system)










#### OPPM Optical Path Protection Switch Module



- Sends the light in two directions at the same time
- Receiver switches source if the preferred direction goes away
- Gives sub second redundancy switch between long and short path on the DWDM ring









## Extend Receivers ethernet ports to DC


- The receiver modules, 119 at each site, has 2x25Gbps SFP+ ethernet ports.
- The the ethernet ports are terminated in a switch and the ring buffer servers are connected to the same switch.
- The switch and ring buffer servers can be moved to a DC and the optical network is used to forward the raw Ethernet from the receivers to the DC.


# Antennas at site, switch and Ringbuffer at DC Logical view





Aggregating eight antenna modules to one 400G optical wave





Receiver site with only 60 antenna modules Aggregating 8 400G waves to one protected line

